



# TARGET ESTIMATE

DATE: 7/1/2022

## PIPELINE & TANK MAINTENANCE

### PROJECT NAME:

Rinse the liner, remove the liner, sand pad, hydroblast and descale for inspection in Tank #2, (1) 73' x 32' AST

COMPANY:	Ceres Solutions Cooperative		
ADDRESS:	3154 Depot Street		
CITY:	Wawaka		
STATE:	Indiana	ZIP:	46794

CUSTOMER:	Mr. Chuck Croy		
PHONE:	(574) 377-2936		
FAX:			
EMAIL:	ccroy@ceres.coop		

## PROJECT DESCRIPTION

- 1) Furnish labor, equipment and materials to mobilize to the facility above.
- 2) **Remove the Liner, Sand Pad, Hydro blast and Descal the tank / tanks listed at the top of the estimate for inspection.**
- 3) The estimate includes, vapor freeing, confined space entry, confined space entry permitting, scaffolding if required, high pressure hot water hydro blast, using a biodegradable cleaner, and a cold water rinse.
- 4) All rinsate will be removed from the tank(s), and placed into containers furnished by the owner and left onsite for proper storage and disposal by the owner.
- 5) Crew to have all required training and certification for confined space entry.
- 6) All materials, removed from the tank such as liner, geo, rinsate, and tank bottoms will be placed into containers provided by the owner, for storage and disposal by the owner.
- 7) Work to be completed per the Daily Rate provided.
- 8) Work to be completed per day for a 3 man crew and equipment for up to 10-hours per day.
- 9) Estimated to take (7) to (9) days.

## BOLIN COMMENTS

- 1) The tank / tanks are to be empty, open and accessible upon arrival.
- 2) The owner is to furnish and adequate water supply, a 115 volt power supply and storage containers for the tank bottoms and rinsate removed from the tank during the cleaning process.
- 3) Both the water and the electric should be located as close as possible to the tank / tanks.
- 4) Proper storage and disposal to be completed by the owner.
- 5) This is estimate does not include abrasive blast cleaning if required.

## CLARIFICATIONS AND EXCEPTIONS

- > Cost associated with labor, equipment, materials, or per diem for the removal of manholes, bolts, gaskets, product, sludges, salts, gels, heal, solids, heavy or impacted scale, nor the installation of manholes, bolts, and gaskets
- > Cost associated with adverse weather conditions
- > Cost associated with Work Permit, LO/TO, or other Operational delays
- > Cost associated with disposal of rinsate, tank bottoms, spent abrasives, contaminated sand, soil, or ground water
- > Cost associated with obstructed entrance to easily access the tank with personnel and equipment.
- > Cost associated with performing any environmental work.
- > Cost associated with fuel surcharge as depicted on our Uniform Rate Sheet as applicable
- > Cost associated with providing gaskets, bolts and nuts, valves, piping, flanges, etc.
- > Cost associated with removal of scale product and/or solids from the tank bottoms or shell
- > Cost associated with landowner contacting and/or damage settlements
- > Cost associated with material delivery delays
- > Cost associated with Pre-job, Site-Specific, and/or company specific orientation, meetings, or training

## PROJECT COST

TARGET ESTIMATE COST	DAYS: 8	\$23,112.00
----------------------	---------	-------------

DAY RATE:	\$2,889.00
-----------	------------

## ACCEPTANCE

- > Bolin Enterprises, Inc. has been contracted by the tank owner and/or operator to Clean and De-scale Tank(s) for inspection, coating, repairs, liner installation, etc. This process is completed using high pressure wash and pumping of the product and rinsate into containers provided by the owner for storage, transportation and disposal by the owner.
- > This notification is to alert the company and/or operator that these tank(s) may/may not have materials in them that cannot be pumped or broken down with water and then pumped. Costs associated with removing solids, sludge, scale or other material, that cannot be pumped, can be provided once information about the amount and type of materials is gathered or provided. Costs to remove these materials is not included in the bid price submitted above.
- > This notification is also verification that the owner is aware that Bolin Enterprises, Inc. will remove the non-pumpable solids and place them on material provided by your company just outside of the tank(s) manhole(s). It is further understood that the removal of these solids that are placed outside of the tank is the sole responsibility of your company and not Bolin Enterprises, Inc. The owner and/or operator is responsible for any and all storage, transportation, and disposal of all materials (e.g. sludge, solids, liquids, rinsate, product, etc.) removed from the tank(s).
- > The signature below provides certification that the owner and/or operator understands the information above and approves the costs involved with removal of non-pumpable solids.
- > The signature below also certifies that he/she has read and understands that non-pumpable materials will be placed outside of the tank as described above, and that the owner and/or operator is responsible for those materials from this point and will assure that these materials are properly stored, contained, removed from the site, and disposed.

\_\_\_\_\_  
Customer Acceptance Signature

\_\_\_\_\_  
Date

Thanks for your consideration; please let me know if you have any questions.

### Scott

Scott Justice | Tank Inspection Compliance Manager

scott.justice@bolininc.com | www.bolininc.com

O 217.932.4533 ext. 318 | C 217.251.6094

BOLIN ENTERPRISES, INC. | 506 NE 15TH STREET | P.O. BOX 70 | CASEY, IL 62420 | O 217.932.4533 | F 217.932.5293 | www.bolininc.com  
PIPELINE, TANK MAINTENANCE & EMERGENCY FUELING 24/7/365



PIPELINE  TANK MAINTENANCE

## TERMS AND CONDITIONS

### 1) PRICES

*Prices quoted are for acceptance within 30 days of quotation date and, unless otherwise specified, are subject to change without notice after that date. It is expressly agreed that there are no expressed nor implied promises, agreements or understandings.*

### 2) SCHEDULING

*Scheduling dates are contingent upon weather, strikes, accidents or other causes beyond our control. We will endeavor to maintain schedules, but will not guarantee schedule.*

### 3) LABOR

*All labor quotations are based on the use of non-union labor: should union labor be required, the amount of the contract will be adjusted accordingly.*

### 4) INSTALLATION

*This installation price does not include any electrical, concrete, blacktop or sewer work, unless stated in the contract.*

### 5) FLOATING

*In the event that the tank should float, during or following application, BEI shall be held harmless. Measures should be taken by OWNER to assure that tank will not float. All expenses for equipment, labor and materials to reinstall tanks shall be borne by the customer.*

### 6) TESTING

*Other than testing of the tank, additional time will be charged on a time and material basis.*

### 7) WINTER CONSTRUCTION

*If because of winter construction it is necessary to remove frost or to protect backfill from freezing, additional expenses involved shall be charged to Buyer on a time and material basis.*

### 8) GROUND CONTAMINATION

*In the event that the ground surrounding the tank is contaminated with any material prior to the BEI application beginning, customer agrees to hold BEI harmless for any liability caused by said ground contamination. In addition, in the event that additional leakage occurs after said coating application customer agrees to hold BEI harmless for ground contamination liability except for repair of tank. Any special corrective action measures and unusual time delays due to said ground contamination shall be at the expense of the customer as billed by our Time and Material rates.*

### 9) DISPOSAL

*Legal disposal by E.P.A. and R.C.R.A. regulations to be determined by owner and associated costs to be born by owner.*

### 10) BUYER

*Buyer (which shall include a general contractor in the event this is a subcontract) shall defend, indemnify and hold harmless BEI, its officers, employees, affiliates, representatives and insurers, from and against all actual or alleged liability, (whether directly or indirectly) which BEI may suffer and incur by reason of bodily injury, including death, to any persons, or by reason of damage to or destruction of any property, including the loss of use thereof, arising out of or in any manner connected with the project of which this contract forms a part.*

### 11) CLAIMS

*Any claims by the buyer against BEI arising from this project or this contract must be brought within (1) one year of BEI's last day of substantial work on this project.*

### 12) TAXES

*Applicable federal, state or municipal taxes are included in proposal.*

### 13) PAYMENT TERMS

*Unless otherwise specified in the contract, terms are net 15 days from the last day of substantial work on project. 2% interest will be added per month on all past due accounts.*